

STRUCTURAL FRAMING PLAN — SAMPLE TAKEOFF

BEAM SCHEDULE

B1 W18x35 Length=6000mm Qty 4 A992

B2 W21x44 Length=7500mm Qty 2 A992

B3 ISMB300 Length=4500mm Qty 6

COLUMN SCHEDULE

C1 W14x82 Height=4500mm Qty 8

C2 UC254x254x73 Height=6000mm Qty 4

BASE PLATE SCHEDULE

BP1 500x500x25 4-M20 Qty 8

BP2 PL 600x600x30 4 Nos M24 Qty 4